

**Request for Quote (RFQ)**  
**Addendum #1- Questions and Answers from Prospective Bidders**

**Labor and Materials for Improvements to the Bombardier Road  
Camel's Hump State Park, Bolton VT**

**July 31, 2018**

---

<b>Date Issued:</b>	<b>July 12, 2018</b>
<b>Non-Mandatory Project Showing:</b>	<b>July 23, 2018</b>
<b>Questions Deadline:</b>	<b>July 30, 2018</b>
<b>Answers Posted by:</b>	<b>August 1, 2018</b>
<b>Bids Due:</b>	<b>August 6, 2018</b>

**Primary Contact:** **Jason Nerenberg**

**Bids to:** VT Department of Forests, Parks & Recreation  
Attn: Jason Nerenberg  
111 West Street  
Essex Junction, VT 05452-4695

State of Vermont  
Vermont Agency of Natural Resources  
Department of Forests, Parks and Recreation (FPR)  
1 National Life Drive, Davis 2  
Montpelier, VT, 05620-3801

## Questions and Answers From Prospective Bidders

Q: What is to be done with fill material coming out of ditches when cleaning? Left within reach of ditch, hauled to approved dump site, or hauled away completely?

A: Material removed from the ditch can be broadcast nearby on the low side of the road, as long as there is no brook in the vicinity. If there is a brook within 50 feet, you'll need to move it a little farther, but I do not anticipate ditch waste leaving the site in a truck, and nearly all will be distributed by excavator bucket.

Q: Will culverts be stockpiled or distributed?

A: Culverts will be distributed by FPR for all sites below the upper landing. All sites above the upper landing will have culverts stockpiled in the landing. Essentially, Culverts for sites 1-14 will be dropped in the landing (the landing is basically site 15) and culverts for sites 16-38 will be brought to the work sites. (See edits in Scope of Services)

Q: Will the roadside be mowed?

A: Yes, FPR will arrange for the road to be mowed prior to work. (See edits in scope of services)

Q: Will there be material for distribution over the culverts?

A: No, material excavated for culvert installation will be spread over the new culverts?

Q: What is meant by "12"- stone"?

A: The specification in this case would be similar or identical to AOT Type I Stone. Stone should vary in size from 1"-12" with at least 50% greater than 4".

Note: Several other edits were made to the scope of services. Edits were made in **red**.